
U356-0755-3x03(00)

PERFORMANCE DATA

To Obtain Performance Data:

- Press and hold the ▼(Down) button.
- While holding the ▼(Down) button for 2 seconds, press and hold the "On/Off" button (hold both buttons simultaneously).
- Use the \triangle (Up) and ∇ (Down) buttons to scroll to the desired performance



Performance Data Table

Performance Data Table				
#	DATA	UNIT		
01	Water Flow Rate	x0.1 gal/min		
02	Outgoing Temperature	°F		
03	Combustion Hours	x100 Hours		
84	Combustion Cycles	See following information		
05	Fan Frequency	Hz		
06	Additional Controllers Connected	See following information		
רם	Water Flow Control Position	0=Mid, 1=Open, 2=Closed		
88	Inlet Temperature	°F		
89	Fan Current	x10 mA		
18	Total Bath Fill Amount	gallons		
11	HEX Outlet Temperature	°F		
15	By-Pass Flow Control Position	Degrees of opening		
14	Intake Thermistor Temperature (Indoor Units Only)	°F		
Ι'Ί	Freeze Protection Temperature (Outdoor Units Only)	°F		
13	Pump Hours	x100 Hours		
50	Pump Cycles	See following information		
		-		

- 0	Pump Cycles				
DISPLAY		CYCLE COUNT			
000	0 to 999	x100 (0 to 99,900)			
10-	to 99-	x10,000 (100,000 to 990,000)			
 	to 5	x1,000,000 (1,000,000 to 6,000,000)			


ı						
	CONTROLLER MODEL	CONNECTED	NOT CONNECTED			
	MC	1	0			
	ВС	_l_	_0_			
	BSC & BSC2	!,	0			

Default display is IDD.


depends on connection status of another controller.


PARAMETER SETTINGS

To Adjust the Parameters:



- 2. Use the \blacktriangle (Up) and \blacktriangledown (Down) button on the controller to select a setting number (See *Parameter* Settings Table)
- Once the desired setting number is selected, use the "On/Off" button on the controller to change the selection for the setting number Example: Display will change from 01A to 01b for Maximum Temperature setting
- To exit the parameters, press the "A" button on the PC board for 1 second.





Parameter Settings Table

SETTING	SETTING DESCRIPTION	SELECTION				
#		R	Ь	C	Р	
01	Maximum Set Temperature	120°F	140°F			
05	High Altitude (Installation Location)	0 - 2,000 ft (0 - 610 m)	2,001 - 5,400 ft (610 - 1,646 m)	5,401 - 7,700 ft (1,646 - 2,347 m)	7,701 - 10,200 ft (2,347 - 3,109 m)	
03	Service Soon	Disabled	0.5 Year	1 Year	2 Years	
04	Recirculation Settings	No Recirculation	Recirculation (Dedicated)	Recirculation (Crossover)		
05	Recirculation Mode	Economy	Comfort			
06	Control Switch	BMS	Air Handler (AH)			
רם	Units in Standby	2	1			
10	Gas Type (Factory Set)	LPG	NG			
15	Water Heater Model	Without Pump	With Pump			
13	(Factory set values and	199/160				
14	not adjustable)	Indoor	Outdoor			
15	Low Activation Mode	On	Off			
16	Pump Speed	Max	High	Medium	Low	
וח	Continuous Recirc Logic Operation	Off	On			
18	Setting Temperature Table	Default	Alternate			
19	Adjust DHW Temperature Setting	0°F (0°C)	1.8°F (1°C)	3.6°F (2°C)	5.4°F (3°C)	
99	Vent Length	Long	Short			

MANIFOLD PRESSURE SETTINGS

electronically controlled and factory pre-set. Under normal circumstances it does not require djustment during installation. Make adjustments only if the unit is not operating correctly and Il other possible causes for incorrect operation have been eliminated.

- Turn off the gas supply.
- Turn off the 120 V power supply. Remove the front panel from the appliance.
- Turn on the 120 V power supply.
- Check the gas type using the data plate on the side of the unit and parameter setting 10 (refer to Parameter Settings section). (A=LPG, b=NG).
- Remove test port screw and attach the manometer to the burner test point, located on the manifold.
- Turn on the gas supply.
- Flow water through the water heater at the maximum flow rate obtainable. (At least 3 gallons per minute is recommended. If there is not enough water flowing, the water heater could shut off or sustain damage due to overheating.)
- Push and hold "B" button. "IF" will appear on the display.
- Push and hold "A" button, "Forced Low" will appear on the display. Push and hold "A" button again. "Forced High" will appear on the display.

the pressure. Use the Down button to decrease the pressure.

- While in "Forced Low" or "Forced High", use the Up button on the controller to increase
- To exit "Forced Low" or "Forced High", push and hold "B" button. "2L" will appear on the
- Push and hold "B" button again. "3C" will appear on the display. (Indoor models only) 15. Push and hold "B" button again. "4t" will appear on the display.
- 16. Push and hold "B" button again. The set temperature will appear on the display (indoor
- models only). Close hot water taps.
- 18. Turn off the gas supply and 120 V power supply.
- Remove the manometer and re-install sealing screw.
- 20. Turn on the gas supply and 120 V power supply. Operate the unit and check for gas leaks.
- Install the front panel.

This appliance must be installed, serviced and removed by a trained and **⚠** WARNING qualified person. During pressure testing of the consumer piping, ensure gas valve is turned off before unit is shut off. Failure to do so may result in serious njury to yourself or damage to the unit.

Manual.

With all gas appliances in operation at maximum gas rate, the following inlet gas pressure at the incoming test point on the Rinnai water heater should read 4 in. W.C. - 10.5 in. wc on natural gas and 8 in. wc -13.0 in. wc on propane gas. If the pressure is lower, the gas supply is inadequate and the unit will not operate to specification. Check the gas meter regulator and pipework for correct operation/sizing and correct as required.

Model	Vent Length	Maximum	Gas Supply Pressure Min./Max.		(FL) Forced Low		(FH) Forced High	
		Water			NG	LPG	NG	LPG
#		Pressure	NG	LPG	inH2O(wc)	inH2O(wc)	inH2O(wc)	inH2O(wc)
REP199i	Short	150 PSI 4.0/10.	4.0/10.5	8.0/13.0	0.72	0.98	2.56	4.24
	Long				0.71	1.00	2.39	3.92
REP160i	Short				0.73	0.96	2.49	4.31
	Long				0.74	0.96	2.55	4.48

ELECTRICAL DIAGNOSTICS

NOTE: Wiring diagram is available in manual and on the inside front cover.

Important Safety Notes

There are a number of (live) tests required when performing electrical diagnostics on this product. Proceed with caution at all times to avoid contact with energized components inside the water heater. Only trained and qualified service technicians should attempt to repair this product. Before checking for resistance readings, disconnect the power source to the unit and isolate the

This unit has freeze protection heaters mounted at different points to protect the water heater

Place one lead of your meter to the flame rod and the others to ground. When the unit is

This unit has two glass fuses located on the PC Board, one inline (10) amp and one (4) amp glass fuse. Remove the fuses and check continuity through it. If you have continuity through each fuse then it is functioning. Otherwise the fuse is blown and must be replaced.

Check all thermistors by inserting meter leads into each end of the thermistor plug. Set your meter to the 20 K scale and read resistance. Applying heat to the thermistor bulb should decrease the resistance. Applying ice to the thermistor bulb should increase the resistance. Below are examples of typical temperatures and resistance readings.

Temperature	Resistance Readings
59°F	11.4 - 14ΚΩ
86°F	6.4 - 7.8ΚΩ
113°F	3.6 - 4.5ΚΩ
140°F	2.2 - 2.7ΚΩ
221°F	0.6 - 0.8ΚΩ

Electrical Circuit Table

WIRE COLOUR

				Connector	PIN
Power Supply	Black-White	AC108∼132V	N/A	CN100	1-3
Flame Rod	Yellow-Body	more than 0.5VAC	N/A	CN9	37
Tiame Rou	Pink-Body	more than 0.5VAC	N/A	CN7	1
Spark Electrode	White-Black	11~14VDC*	N/A	CN9	5-8
	Red-Black	7∼48VDC*	N/A	CN9	1-3
Combustion Fan	White-Black	2∼14VDC*	N/A	CN9	2-3
	Yellow-Black	11~14VDC	N/A	CN9	4-3
	Red-Pink	N/A	40∼60Ω	CN9	21-19
Water Flow	Blue-White	1974	40 0012	CN9	25-23
Control Device	Orange-Grey	11~14VDC	N/A	CN9	6-13
	Brown-Grey	limitter On: less than 1VDC limitter Off: $4\sim$ 6VDC	N/A	CN9	17-13
By-Pass Flow	Red-Pink			CN9	29-27
Control Device (RE199, RE180 model only)	Blue-White	N/A	40~60Ω	CN9	33-31
Main Solenoid Valve	Black-Black	8∼13.5VDC	15∼25Ω	CN9	18-32
Modulating Solenoid Valve	Yellow-Yellow	2∼17VDC*	10∼20Ω	CN9	12-14
Solenoid Valve 1	Blue-Black	8∼13.5VDC	20~30Ω	CN9	24-22
Solenoid Valve 2	Yellow-Black	8∼13.5VDC	20∼30Ω	CN9	26-22
Solenoid Valve 3	Red-Black	8∼13.5VDC	20∼30Ω	CN9	28-22
Solenoid Valve 4 (RE/REP199, RE180 model only)	Orange-Black	8∼13.5VDC	20~30Ω	CN9	30-22
Outgoing Water	White-White		59°F: 11.4-14kΩ	CN7	11-13
Thermistor	White-White		86°F: 6.4-7.8kΩ	CN7	4-5
Inlet Thermistor	White-White		113°F: 3.6-4.5kΩ 140°F: 2.2-2.7kΩ	CN7	9-6
Heat Exchanger Thermistor	White-White		221°F: $0.6-0.8k\Omega$ Disconnect the con-	CN7	8-4
Intake Thermistor (Indoor type only)	White-White	N/A	nector and measure at thermistor side.	CN7	12-6
Freeze Protection Thermistor (Outdoor type only)	White-White		32°F: 38k-43k 50°F: 22k-26k 68°F: 14k-17k Disconnect the con- nector and measure at thermistor side.	CN7	10-6
Overheat Switch	Black-Black	less than 1VDC	less than 1Ω	CN9	10-16
	Red-Black	11~14VDC		CN9	7-11
Water Flow Sensor	Yellow-Black	4∼7VDC* Comment: more than 6Hz (1.0L/min)	N/A	CN9	9-11
Integrated Pump	White-Black	AC108~132V	N/A	C101	1-2
(Integrated Pump type only)	Red-Brown	11~14VDC*	N/A	CN8	1-2
External Pump (Except for integrated pump and RE140 model)	White-Black	AC108∼132V*	N/A	C101	1-2
					4.0
Additional Controller(s)	White-White	11~14VDC	N/A	CN4	1-3

DIAGNOSTIC CODES

To Display Diagnostic Codes:

- 1. Turn off the water heater by pressing the "On/Off" button.
- 2. Press and hold the "On/Off" for 2 seconds and then the \triangle (Up) button simultaneously.
- 3. The last 9 maintenance codes display and flash one after the other.
 - the \triangle (Up) button simultaneously.
- 4. To exit diagnostic codes and return the water heater to normal operation, press and hold the "On/Off" button for 2 seconds and then 5. Turn on the water heater by pressing the "On/Off" button.

Air Supply or Exhaust Blockage

- Ensure approved venting materials are being used.
- Check that nothing is blocking the flue inlet or exhaust.
- Check all vent components for proper connections.
- Ensure vent length matches with the vent lengths set in the parameter settings.
- Verify High Altitude setting is set properly. (See Parameter Setting)
- · Check fan for blockage.

No Ignition (Heater Not Turning On)

- Check that the gas is turned on at the water heater, meter, or propane cylinder.
- If the system is propane, make sure that gas is in the tank • Bleed all air from the gas line
- Ensure appliance is properly grounded
- Ensure gas type and pressure is correct.
- Ensure gas line, meter, and/or regulator is sized properly.
- Verify parameter setting are set properly Ensure igniter is operational.
- Check igniter wiring harness for damage.
- Check gas solenoid valves for open circuits
- Ensure flame rod wire is connected.
- Check flame rod for carbon build-up. • Remove burner cover and ensure burners are properly seated.
- Remove burner plate; inspect burner surface for condensation/debris. Check the ground wire for the PC board.

No Flame

- Check that the gas is turned on at the water heater, meter, or cylinder.
- Check for obstructions in the flue outlet
- If the system is propane, make sure that gas is in the tank.
- Ensure gas line, meter, and/or regulator is sized properly.
- Ensure gas type and pressure is correct. Bleed all air from gas lines.
- Ensure proper venting material was installed.
- Ensure condensation collar was installed properly. • Ensure vent length is within limits.
- Verify parameter setting are set properly
- Check power supply for loose connections • Check power supply for proper voltage and voltage drops.
- Ensure flame rod wire is connected.
- Check flame rod for carbon build-up. • Disconnect and reconnect all wiring harnesses on unit and PC board.
- Check gas solenoid valves for open circuits.
 Remove burner plate; inspect burner surface for condensation/debris.

- Check for restrictions in air flow around unit and vent terminal.
- Check gas type of unit and ensure it matches gas type being used. • Check for low water flow in a circulating system causing short-cycling.
- Check for foreign materials in combustion chamber and exhaust piping. Check heat exchanger for cracks or separations.
- Check heat exchanger surface for hot spots which may be caused by scale build-up. Refer to instructions in manual for flushing heat exchanger. Hard water must be treated to prevent scale build up or damage to the heat exchanger.
- Measure resistance of safety circuit.
- Ensure high fire and low fire manifold pressure is correct.

Check for improper gas conversion of product.

- High Outgoing Temperature
 - Check for restrictions in air flow around unit and vent terminal. • Check for low water flow in a circulating system causing short-cycling.
 - Check for foreign materials in combustion chamber and exhaust piping. Check for blockage in the heat exchanger.
- Check the thermistor sensor and clean sensor of scale build-up. Electrical Grounding
- Check all components for electrical short.

Outgoing Water Temperature Thermistor

- Check sensor wiring for damage. Measure resistance of sensor. (See Electrical Diagnostics)
- Clean sensor of scale build-up. Replace sensor if necessary.

Heat Exchanger Thermistor

- Check sensor wiring for damage.
- Measure resistance of sensor. (See Electrical Diagnostics)
- Replace sensor if necessary.

Combustion Air Temperature Thermistor Fault

- Check for restrictions in air flow around unit and vent terminal.
- Check sensor wiring for damage. Measure resistance of sensor
- Ensure fan blade is tight on motor shaft and is in good condition. Replace sensor if necessary.

Freeze Protection Thermistor

- Check sensor wiring for damage.
- Measure resistance of sensor. (See Electrical Diagnostics) • Replace sensor if necessary.
- *See "Flectrical Diganostics"

Inlet Water Temperature Thermistor

Replace sensor if necessary.

Visit www.rinnai-lms.com for additional troubleshooting resources

• Check wiring harness to motor for damaged and/or loose connections. Measure resistance of motor winding.

- Ensure the inlet water filter is clean and free of debris.
- Ensure parameter setting are correctly set for recirculation mode. Ensure pump supply voltage.
- connections.Ensure air is removed from the recirculation line.

- Measure the resistance values and voltage of the water flow control.* Ensure the harness and connector are not wet.
- If the voltage from the PC Board is abnormal, replace the PC Board; otherwise, replace the water flow servo valve.
- Measure the resistance values and voltage of the bypass servo valve.*

- PC Board
- Solenoid Valve Circuit
- Check gas solenoid valves for short circuits or grounding.
- Flame Sensing Device
- Check the flame rod and wire for damage.
- Check the resistance to the cabinet.
- If there is no issue with the flame rod or wiring, replace the PC Board.

• Turn off water supply and contact licensed professional.

- LC indicates that there is scale build up in the heat exchanger and that the heat exchanger needs to be flushed to prevent damage. Refer to the flushing instructions in the manual. Hard water must be treated to prevent scale build up or damage to
- the heat exchanger.

 After flushing, reset LC code as instructed.


 Please call Rinnai technical department.

- 55 is a time-based service indicator set during installation. See section "4.10 Configure Parameter Settings" for additional details on setting and changing the $55\,$
- prevent damage (refer to section "6.2 Flushing the Heat Exchanger" for more information). Hard water must be treated to prevent scale build-up or damage to
- the heat exchanger • To reset the 55 code, push the On/Off button on the temperature controller 5 times

NO CODE - Nothing happens when water flow is activated

- Clean inlet water supply filter.
- On new installations ensure hot and cold water lines are not reversed. Verify you have at least the minimum flow rate required to fire unit.
- bleed over in your plumbing.
- Verify turbine spins freely. Measure the resistance of the water flow control sensor.

- Placeholder in Diagnostic code history indicating that a service provider performed
- Enter this code after performing service by pressing ▲ (Up), ▼ (Down) and On/Off
- FF is visible on the monitor.



°F/°C ○ In Use

FF

from freezing. All of them should display a positive resistance reading. Flame Rod attempting to ignite, you should read more than 0.5VAC.

Temperature	Resistance Readings
59°F	11.4 - 14ΚΩ
86°F	6.4 - 7.8ΚΩ
113°F	3.6 - 4.5ΚΩ
140°F	2.2 - 2.7ΚΩ
221°F	0.6 - 0.8ΚΩ

Measure resistance of sensor. (See Electrical Diagnostics)

Modulating Solenoid Valve Signal

• Check modulating gas solenoid valve wiring harness for loose or damaged terminals. Measure resistance of valve coil.

Combustion Fan

Ensure fan will turn freely.

Recirculation Low Flow

 Ensure pump speed parameter settings are set properly. • Check the wiring harness to the pump and PCB for damaged and/or loose

Water Flow Servo

Bypass Flow Servo

- Ensure the harness and connector are not wet. If the voltage from the PC Board is abnormal, replace the PC Board; otherwise,
- Check the connection harness at the connection on the PC board.
- Ensure dip switch on PC board is in the OFF position.
- Ensure heater circuit is not grounded.
- Verify flame rod is touching flame when unit fires.
- Remove flame rod; check for carbon build-up; clean with sand paper. • Check inside burner chamber for any foreign material blocking flame at flame rod.

79 Water Leak Detected


- Scale Build-up in Heat Exchanger (when checking maintenance code history, "00" is

- (SS) Service Soon (Flush Heat Exchanger)
 - 55 indicates that it is time for service. The heat exchanger should be flushed to

- Check for cold to hot cross over. Isolate circulating system if present. Turn off cold

If the display is blank and clicking is coming from the unit, disconnect the water flow servo motor (GY, BR, O, W, P, BL, R). If the display comes on then replace the

FF Maintenance Indicator



Rinnai America Corporation continually updates materials, and as such, content is subject to change without notice. For further information, contact Rinnai at 1-800-621-9419 or visit www.rinnai.us

000 UTEM 0006 0007 0007 0008 0009 0011 0011 0011 0011 0011 1010 1010 1110 1111 1111 1111 1111 1111 1111 1111 1111	
Wall Bracket Reinforcement Plate Front Panel Upper Packing Front Panel Upper Packing Front Panel Lower Packing Temperature Control Temperature Control Plate Earth Plate Latch Hook Latch Hook Latch Hook Latch Hook Latch Hook Clamp Fixing Plate Clamp Rubber Stop Combustion Chamber Stay Gas Control Assembly Test Port Set Screw 3/4 Gas Inlet Burner Unit Assembly - Small Combustion Gasket - Right Burner Unit Assembly - NG Manifold Assembly - Right Electrode Bracket - Right Electrode Bracket - Right Electrode Bracket - Left Back Pressure Connector Trube H Electrode Bracket - Right Electrode Bracket - Right Electrode Bracket - Right Back Pressure Connector Fan Casing Combustion Chamber Bracket - Right Combustion Chamber Bracket - Left Combusti	
109001254 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
ITEM Duct Bracket - Small 141 Duct Bracket - Small 143 Heat Exchanger Assembly - Small 144 Flue Connection Assembly 145 Inlet Seal 146 O-ring 147 Pipe Seal 147 Pipe Seal 148 Cap 149 Packing 140 Water Flow Servo & Sensor 401 Water Flow Servo & Sensor 402 Rectifier 405 Plug Band 406 Ø16 Pipe Bracket 401 Water Flow Servo & Sensor 402 Rectifier 405 Plug Band 406 Ø16 Pipe Bracket 410 Gas Pipe Bracket 411 Bracket 411 Bracket 412 Filter Assembly 413 Cover 415 Hot and Cold Water Pipe Assembly 416 Water Flow Turbine 477 Pump Connection 470 Pump Connection 471 Anti-vibration Stand 472 Pump Connection 473 Clip 474 Clip 475 Pump Connection 476 Pump Connection 477 Pump Connection 482 Drain Plug 700 PC Board - Large 700 PC Board - Subject to change wit	en replacing the heat exchanger, therma
PART NUMBER 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	Thermal If truse must be properly insta
TITEL 704 Pump Circuit Plate 706 Ignitor 707 High Tension Cord 708 Electrode Sleeve 709 Water Inlet Thermistor 710 Heater Clip 711 Clip 714 Fuse Holder 715 Heater Clip 716 Heater Clip 717 Heater Clip 717 Heater Clip 717 Heater Clip 718 Gas Control Harness 720 Power Cord Assembly 721 Intake Air Thermistor 724 Sensor Harness - 1 725 Fuse Harness - 7 726 Power Supply Harness - 3 727 Ignitor Bracket 729 Cable Clip 730 Twin Thermistor 731 Solenoid Harness 732 Ignitor Bracket 733 Pump Harness 731 Solenoid Harness 732 Ignitor Bracket 733 Pump Harness 734 Over Heater 735 Ignitor Bracket 736 Power Supply Harness 731 Solenoid Harness 732 Ignitor Bracket 733 Ignitor Bracket 734 Over Heater 735 Ignitor Bracket 736 Power Supply Harness 737 Ignitor Bracket 738 Ignitor Bracket 739 Ignitor Bracket 730 Ignitor Bracket 730 Ignitor Bracket 731 Ignitor Bracket 732 Ignitor Bracket 733 Ignitor Bracket 734 Over Heater 735 Ignitor Bracket 736 Ignitor Bracket 737 Ignitor Bracket 738 Ignitor Bracket 739 Ignitor Bracket 730 Ignitor Bracket 730 Ignitor Bracket 731 Ignitor Bracket 732 Ignitor Bracket 733 Ignitor Bracket 734 Ignitor Bracket 735 Ignitor Bracket 736 Ignitor Br	al Fuse Location Stalled and secured. Refer to the following Illust
PART NUMBER 105000964 1 1 1 1 105000963 1 1 1 1 1 105000964 1 1 1 1 1 105000965 1 1 1 1 1 105000965 1 1 1 1 1 105000965 1 1 1 1 1 105000966 1 1 1 1 1 105000976 1 1 1 1 105000977 1 1 1 105000977 1 1 1 105000986 1 1 1 1 105000988 1 1 1 1 105000988 1 1 1 1 105000988 1 1 1 1 105000988 1 1 1 1 105000988 1 1 1 1 105000988 1 1 1 1 105000988 1 1 1 1 1 105000988 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	places
Screw DESCRIPTION	athves.
ZFDB0408UK 10 109001306 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	Be careful of bhing becomethin the heat each of the heat